## HASSAN DISTRICT.

*Dated 12th April 1920.*

Notice is hereby given that sealed tenders will be received at the Office of the President District Board, Hassan, up to 1st May 1920, for constructing a first class musafirkhana near the Railway Station at Hassan.

2. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1921.

3. The plan is of approved design. This and the detailed estimate of quantities and conditions may be seen at the Office of the President of the District Board, Hassan, between the hours of 12 noon and 5 P.M. on all working days.

4. Tenders should be submitted in the form which may be obtained from the Office of the President, District Board, Hassan, or from the Office of the Amildar, Hassan Taluk, and must show the rates at which the different items specified will be executed.

5. Each tender must be accompanied by a deposit of Rs. 100 (one hundred) only in cash as earnest money and be superscribed "Tender for constructing the 1st class musafirkhana at Hassan," otherwise the tender will be rejected.

6. The final acceptance of any tender will rest with the President, District Board, Hassan, who does not bind himself to accept the lowest or any tender, or to assign any reason whatever for the rejection of any tender.

7. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled and his earnest money will be forfeited to the District Board.

8. The name of the successful competitor, whose tender has been accepted will be posted on the notice board at the Office of the President of the District Board, Hassan, in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

9. On acceptance of one of the tenders the earnest money on rejected tenders will be returned.

Abstract estimate for constructing a first class musafirkhana at Hassan.

| No. | Items of work | Per | Quantity | Rate Rs. | a. | p. |
|---|---|---|---|---|---|---|
| 1 | Earthwork excavation for foundation and filling in basement | C. yd. | 100 | | | |
| 2 | Stone in mud filling in foundation | C. ft. | 2,704 | | | |
| 3 | Do " basement | " | 2,032 | | | |
| 4 | Burnt stone slabs dressed 6" thick | S. ft. | 521 | | | |
| 5 | Burnt brick in clay | C. ft. | 5,579 | | | |
| 6 | Burnt brick in mortor | " | 961 | | | |
| 7 | Chunam coping | R. ft. | 122 | | | |
| 8 | Jungle wood doors and windows battened with iron bars, etc., complete. | Sqr. | 396 | | | |
| 9 | Honne wood work wrought and put up | C. ft. | 271·61 | | | |
| 10 | Roofing with 1st class Mangalore tiles on teak reepers, etc., complete. | Sqr. | 40·50 | | | |
| 11 | Ridge tiles set in mortor | R. ft. | 300 | | | |
| 12 | Ventilating tiles | No. | 12 | | | |
| 13 | Pointing with chunam | Sqr. | 7·58 | | | |
| 14 | Whitewashing as per plastering | " | 118·70 | | | |
| 15 | Flooring with 1st class Mangalore tiles on bed of 3" concrete | " | 20·00 | | | |
| 16 | Chokolate painting | " | 7·92 | | | |
| 17 | Stone pillars dressed and fixed | S. ft. | 57 | | | |
| 18 | Jungle wood gate (varies according to type design) | " | 30 | | | |
| 19 | Do do | " | 128 | | | |
| 20 | Plastering with chunam | Sqr. | 111·12 | | | |
| 21 | Tarring wood work | L. S. | | | | |
| 22 | Providing and fixing Cuddapah slabs for bathing cisterns mill and mill stone ovens, etc., complete. | " | | | | |
| 23 | Levelling ground and opening drains | " | | | | |
| | *Constructing stables, latrine and coach house to musafirkhana.* | | | | | |
| 1 | Earthwork excavation for foundation | C. yd. | 41 | | | |
| 2 | Concrete in mortar do | C. ft. | 548 | | | |
| 3 | Stone in mud do | " | 412 | | | |
| 4 | Burnt brick in clay superstructure | " | 1,673 | | | |
| 5 | Honnewood work wrought and put up, complete, with wood oiling | " | 76·67 | | | |
| 6 | Roofing with 1st class Mangalore tiles on teak reepers | Sqr. | 10·87 | | | |
| 7 | Ridge tiles set in mortar | R. ft. | 54 | | | |
| 8 | Chunam borders | " | 84 | | | |
| 9 | Chunam plastering | Sqr. | 30·78 | | | |
| 10 | White and colorwashing as per plastering | " | 30·78 | | | |
| 11 | Gravelling flooring | " | 4·20 | | | |

| No. | Items of work | Per | Quantity | Rate Rs | a. | p. |
|---|---|---|---|---|---|---|
| 12 | Providing and fixing burnt stone posts dressed 6" thick 7' long, etc., complete. | Sqr. | 4 | | | |
| 13 | Providing bamboos, etc., and cutting holes for the stone posts .. | L. S. | | | | |
| 14 | Flooring with cement plastering over 3" concrete, etc., complete .. | Sqr. | 72 | | | |
| 15 | Providing surki concrete drain .. | L. S. | | | | |
| 16 | Burnt stone slabs 3" thick .. | S. ft. | 11 | | | |
| 17 | Coping with burnt brick in mortar including chunam plastering .. | R. ft. | 14 | | | |
| | *Excavating the well.* | | | | | |
| | Earthwork excavation for foundation, 1st fathom .. | C. yd. | 81 | | | |
| | Do 2nd " .. | " | 81 | | | |
| | Do 3rd " .. | " | 32 | | | |
| | Do 4th " .. | " | 32 | | | |
| | Do 5th " .. | " | 32 | | | |
| | Do 6th " .. | " | 32 | | | |
| | Do 7th " .. | " | 32 | | | |
| | Do 8th " .. | " | 32 | | | |
| | Last portion .. | " | 11 | | | |
| | Burnt stone steming including jelly .. | C. yd. | 97 | | | |
| | Puddle clay filling .. | " | 130 | | | |
| | Good earth filling .. | " | 83 | | | |
| | Concrete in mortar .. | C. ft. | 177 | | | |
| | Opening a concrete drain with cement plastering .. | R. ft. | 106 | | | |
| | Burnt stone slabs 4" thick .. | S. ft. | 361 | | | |
| | Do 6" .. | " | 44 | | | |
| | Burnt brick in mortar parapet well .. | C. ft. | 103 | | | |
| | Chunam plastering .. | Sqr. | 1·52 | | | |
| | Providing pulleys with iron straps, etc., complete .. | | | | | |
| | Cutting holes for the slabs .. | L. S. | | | | |
| | Bailing out water .. | " | | | | |

N. S. NANJUNDIAH,
For *President, District Board.*

## MYSORE CITY IMPROVEMENT TRUST BOARD.

*Notification No.* 375-*M.* 186—*C.* 155 *of* 19-20, *dated* 15*th April* 1920.

1. Under Section 16 (1) of the City of Mysore Improvement Regulation, III of 1903, it is hereby notified that a scheme has been made for the improvement of Kannegowdanakoppal village situated within the Municipal limits of Mysore City. The portion proposed to be improved is bounded on the east by the Railway line and Law Courts, on the west by the Distillery road and fields, on the north by the Chamaraja road and Exhibition Grounds, on the south by Survey Nos. 192, 191 of Kannegowdanakoppal village and katte.

2. The particulars of the scheme, a map of the area comprised therein and the statements specifying the land, etc., proposed to be acquired may be seen at the Chairman's Office located in the Rangacharlu Memorial Hall during office hours.

---

*Notification No.* 379-*M.* 188—*C.* 165 *of* 19-20, *dated* 15*th April* 1920.

Under Section 16 of the City of Mysore Improvement Regulation of 1903, it is hereby notified that the property of Darji Subbamma in block No. 33, Devaraj Mohalla, Mysore City, is required for effecting a further improvement in the scheme sanctioned in Government Proceedings No. 7191-3—Ml. 189-06-3, dated the 8th February 1907.

The property specified in the above is bounded on the east by Davood Sab's house, west by Conservancy lane, north by Trust land and south by lane. The plan of these properties can be seen at the Chairman's Office during office hours, located at Rangacharlu Memorial Hall, Mysore.

C. SRIKANTESWARA AIYAR,
*Chairman.*

## SHIMOGA DISTRICT.

*Notification dated 7th April* 1920.

The right to collect tolls at the toll-gate near Badadabyle with sub-toll-gate at Karadigere sanctioned in Government Order No. 6434-5—L. B. 105-15-3, dated 5th April 1917, on the Sorab-Siddapur road in the Sorab Taluk, from 1st July 1920 to 30th June 1921, will be sold by public auction at the Taluk Cutcherry at Sorab by the Deputy Commissioner or Assistant Commissioner, deputed by him for the purpose on Tuesday the 25th May 1920.